

## **SERVICES REQUIRED FROM THE CLIENT**

- 1. A reasonably level floor.**
- 2. Water supply as described in the plant production data sheet connected to the backwater tank.**
- 3. Electricity supply as described in the plant Production Data sheet connected to the main breaker supplied in the plant electrical panel at the specified voltage and hertz.**
- 4. Compressed air as described in the plant production data sheet connected to the receiver supplied.**
- 5. A sump or drainage for accidental effluent spills. (The system is a closed circuit and normal effluent would consist of small amounts of seal water from pumps).**
- 6. One 500 x 500mm openings through the roof with ducting for cooling tower exhausts which must be weather proofed after installation.**
- 7. Off-loading facilities on arrival of containers and a 2.5 ton forklift during construction. A list of hand tools and electrical appliances required during construction will be provided.**
- 8. A crew of 2 skilled construction workers for the duration of the installation and commissioning including a qualified electrician to work under the supervision of Pulptech Limited technicians.**
- 9. Return business class airfares, local transport, interpreter if necessary and acceptable accommodation with full board for Pulptech Limited technician and commissioning engineer**
- 10. The acquisition of all local licenses and permits.**
- 11. Insurance to cover all risks during construction including damage or loss to new and existing equipment and buildings.**
- 12. All loading and shipping costs from S.P.M.'s Cape Town factory to end destination.**
- 13. Access to fax and telephone facilities (costs for Pulptech Limited account).**

